SAFE HARBOR MASTER PLAN & ADMINISTRATIVE SUBDIVISION

GLENCO ROAD, FLORA STREET & WHARF ROAD WARWICK, RHODE ISLAND AUGUST, 2023

INDEX SHEET:

SHEET 1 OF 5 EXISTING CONDITIONS PLAN

SHEET 2 OF 5 SITE PLAN

SHEET 3 OF 5 DETAIL PLAN 1

SHEET 4 OF 5 DETAIL PLAN 2

SHEET 5 OF 5 400' RADIUS PLAN


SHEET 1 OF 1 ADMINISTRATIVE SUBDIVISION PLAN

GREENWICH BAY MARINA EAST YARD PLAT

SHEET 1 OF 1 ADMINISTRATIVE SUBDIVISION PLAN

WHARF MARINA PLAT

SHEET 1 OF 1 MARINA PERIMETER LIMIT PLAN



I HEREBY CERTIFY THAT THIS SURVEY WAS ACTUALLY MADE ON THE GROUND
AS PER RECORD DESCRIPTION AND IS CORRECT. THERE ARE NO
ENCROACHMENTS EITHER WAY ACROSS PROPERTY LINES EXCEPT AS
SHOWN.

08/24/2023

BY: REGISTERED PROFESSIONAL LAND SURVEYOR

DATE

A.P. 359, LOTS 292-303, 305, 306, 555 & 556 OWNER / APPLICANT: SHM GREENWICH BAY, LLC 14875 PRESTON ROAD, SUITE 975 DALLAS, TEXAS 75254


RIGL 34-13-1
ABUTTING STREET INDEX


1. SADDLEBROOK DRIVE
2. GREEN BUSH ROAD

COPYRIGHT

WATERMAN ENGINEERING CO.
CIVIL ENGINEERS & SURVEYORS

46 SUTTON AVENUE EAST PROVIDENCE, RI 02914-2096 THESE DRAWINGS ARE THE PROPERTY OF THE ENGINEER/SURVEYOR AND HAVE BEEN PREPARED FOR THE OWNER, FOR THIS PROJECT AT THIS SITE AND ARE NOT TO BE USED FOR ANY OTHER PURPOSE, LOCATION OR OWNER WITHOUT WRITTEN CONSENT OF THIS OWNER OR ONE OF IT'S DIRECTORS'





** SIGNATURES MUST BE IN BLUE INK TO CONSTITUTE AN ORIGINAL PLAN

CERTIFICATION

THIS SURVEY HAS BEEN CONDUCTED AND THE PLAN HAS BEEN PREPARED PURSUANT TO 435-RICR-00-00-1.9 OF THE RULES AND REGULAT.

435-RICR-00-00-1.9 OF THE RULES AND REGULATIONS ADOPTED ADOPTED BY THE RHODE ISLAND STATE BOARD OF REGISTRATION FO PROFESSIONAL LAND SURVEYORS ON APRIL 28, 2018, AS FOLLOWS:

TYPE OF BOUNDARY SURVEY:
COMPREHENSIVE BOUNDARY SURVEY

EVEY /

OTHER TYPE OF SURVEY:
DATA ACCUMULATION

DATA ACCUMULATION TOPOGRAPHIC SURVEY PLAN

THE PURPOSE FOR CONDUCTING THIS SURVEY AND FOR THE PREPARATION OF THE PLAN IS AS FOLLOWS:

TO MERGE THE ABANDONED FLORA ST. AND WITH A.P. 359, LOTS 292-303, 305-306, 555 & 556 INTO PARCEL 'A' AS SHOWN.

BY:


RICHARD S. LIPSITZ, P.L.S.
WATERMAN ENGINEERING COMPANY (COA No. LS.000A483)


RICHARD S. LIPSITZ, P.L.S.
DATE

CITY OF WARWICK, R.I.

MASTER PLAN SUBMISSION &
ADMINISTRATIVE SUBDIVISION







DUST CONTROL NOTES

L. ROBERT SMITH

REGISTERED

PROFESSIONAL ENGINEER

* SIGNATURES MUST BE IN BLUE INK

ON AN AS-NEEDED BASIS OR AS DIRECTED BY CRMC, RIDEM OR OWNER, THE CONTRACTOR SHALL UTILIZE ONE OF THE FOLLOWING METHODS TO CONTROL DUST:

A. THE EXPOSED SOIL SURFACE SHOULD BE MOISTENED PERIODICALLY WITH ADEQUATE WATER TO CONTROL DUST.

B. CALCIUM CHLORIDE SHOULD BE EITHER LOOSE DRY GRANULES OR FLAKES FINE ENOUGH TO FEED THROUGH A SPREADER AT A RATE THAT WILL KEEP SURFACE MOIST BUT NOT CAUSE POLLUTION OR PLANT DAMAGE.

THE METHODS SHOULD BE REPEATED AS NEEDED, AND SPECIAL ATTENTION MUST BE GIVEN TO THE ACCESS DRIVES.

INSPECTION/MAINTENANCE NOTES

- SHALL BE PLACED TO PREVENT SEDIMENT FROM ENTERING THE ABUTTING PROPERTIES AND WATERS.
- 2. EXTREME CARE SHALL BE EXERCISED SO AS TO PREVENT ANY UNSUITABLE MATERIAL FROM ENTERING THE DRAINAGE SYSTEM OR ABUTTING WATERS.

RAIN GARDEN SHOULD BE LOCATED:

- 3. ALL DISTURBED AREAS WHICH BECOME SUBJECT TO EROSIVE TENDENCIES WHETHER THEY BE NEWLY FILLED OR EXCAVATED SHALL RECEIVE SLOPE PROTECTION - SUCH AS
- 4. DURING CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING DRAINAGE AND RUNOFF FLOW DURING PERIODS OF RAINFALL
- 5. DURING CONSTRUCTION, THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL EROSION CONTROL MAINTENANCE AND SHALL INSPECT / REPLACE DAILY DURING CONSTRUCTION, FOLLOWING RAINFALL AND WEEKLY DURING NON-CONSTRUCTION PERIODS.
- ADDITIONAL FILTER SOXX OR SANDBAGS SHALL BE LOCATED AS CONDITIONS WARRANT OR AS DIRECTED BY THE ENGINEER.
- 7. THE LATEST VERSION OF THE "RHODE ISLAND SOIL EROSION AND SEDIMENT CONTROL PRIOR TO COMMENCING GRUBBING OPERATIONS AND EARTHWORK, FILTREXX FILTER SOXX HANDBOOK" PREPARED BY THE R.I. STATE CONSERVATION COMMITTEE, MUST BE UTILIZED BY THE CONTRACTOR AS A GUIDE.
 - 8. THE CONTRACTOR IS RESPONSIBLE FOR ALL DUST CONTROL AND FOR THE ENTIRE PROJECT DURATION, INCLUDING TEMPORARY SHUT-DOWN PERIODS, MUST MONITOR AND REPAIR, AS NEEDED, ALL SLOPES TO ENSURE A STABLE PRODUCT.

GENERAL PROJECT WIDE NOTES

- CONTRACTOR SHALL INSTALL TEMPORARY MEASURES SUCH AS; FIBER MATTING, CRUSHED STONE, HAY OR STRAW IN AREAS WHERE SLOPES OR STABILIZATION HAS FAILED.
- FILTER SOXX (OR SILT FENCE OR STAKED HAYBALES) SHALL BE INSTALLED AROUND THE PERIMETER OF THE AREA TO BE DISTURBED BY CONSTRUCTION. ADDITIONAL APPLICATIONS OF THESE CONTROL MEASURES MAY BE REQUIRED DURING THE CONSTRUCTION PROCESS. THE CONTRACTOR SHALL INSPECT THE SITE AT A MINIMUM OF ONCE PER WEEK OR WITHIN 24 HOURS
- IF EROSION OR EROSIVE TENDENCIES ARE APPARENT ON THE SITE, THE CONTRACTOR IS RESPONSIBLE TO INSTALL ADDITIONAL CONSTRUCTION BMP'S SUCH AS SAND BAGS AS DIRECTED BY RIDEM, CRMC OR ENGINEER DURING CONSTRUCTION.
- IF SEDIMENT OR DEBRIS IS TRACKED ONTO EXISTING PAVED AREAS ADJACENT TO THE CONSTRUCTION AREA, THE CONTRACTOR IS REQUIRED TO SWEEP THE PAVEMENT ON A DAILY BASIS. THE AREA SHALL BE INSPECTED DAILY.
- 5. THE CONTRACTOR IS RESPONSIBLE TO KEEP THE SITE CLEAN OF TRASH. RECOMMENDED DAILY PATROL OF THE CONSTRUCTION SITE SHOULD BE CONDUCTED TO PICK-UP TRASH. THE OPERATOR SHALL REQUIRE THE CONTRACTOR TO HAVE PORTABLE SANITARY FACILITIES ON SITE. ROUTING CLEANING AND WASTE DISPOSAL OF THESE FACILITIES IS REQUIRED.

FILTREXX SOXX NOTE

CONTRACTOR IS RESPONSIBLE TO BECOME FAMILIAR WITH THE FILTREXX PRODUCTS AND COORDINATE INSTALLATION SCHEDULES AND METHODS WITH THE ENGINEER PRIOR TO PLACEMENT.

EROSION CONTROL AND SOIL STABILIZATION PROGRAM

- 1. EXTREME CARE SHALL BE EXERCISED SO AS TO PREVENT UNSUITABLE MATERIAL FROM ENTERING THE DRAINAGE SYSTEM, NEARBY WATERS, ADJACENT PROPERTY AND ROADWAYS.
- 2. TEMPORARY TREATMENTS SHALL CONSIST OF A HAY, STRAW, OR FIBER MULCH PROTECTIVE COVERS, SUCH AS A MAT OR FIBER LINER (BURLAP, JUTE, FIBERGLASS NETTING, EXCELSIOR BLANKETS). THEY SHALL BE INCORPORATED INTO THE WORK AS WARRENTED OR AS ORDERED BY THE OWNER.
- 3. HAY OR STRAW APPLICATIONS SHALL BE IN THE AMOUNT OF 3,000 4,000 LBS./ACRES.
- 4. STOCKPILES SHALL HAVE SLOPES NO STEEPER THAN 2:1 AND SHALL BE SURROUNDED BY STAKED HAY BALES OR SILT FENCING
- 5. STOCKPILES EXPOSED FOR EXCESSIVE PERIODS SHALL RECEIVE TEMPORARY TREATMENT CONSISTING OF HAY, STRAW OR FIBER MATTING.
- 6. DURING CONSTRUCTION, THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL EROSION CONTROL MAINTENANCE AND SHALL INSPECT / REPLACE AS NEEDED.
- 7. ADDITIONAL HAY BALES OR SANDBAGS SHALL BE LOCATED AS CONDITIONS WARRENT OR AS DIRECTED BY THE ENGINEER, OWNER, MUNICIPAL REPRESENTATIVES, RIDEM OR CRMC.
- 8. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING DUST CONTROL AT NO ADDITIONAL COST TO THE OWNER.
- 9. ALL PROPOSED CATCH BASINS AND EXISTING CATCH BASIN ADJACENT TO THE CONSTRUCTION AREA SHALL BE PROTECTED BY STAKED HAY BALES, SILT FENCING OR SILT SACKS.
- 10. THE FILTREXX FILTER SOXX MAY BE INSTALLED ON THE EXISTING PAVEMENT / IMPERVIOUS AREAS WITH OUT STAKES. CONTRACTOR SHALL INSPECT DAILY, IF SOIL EROSION OR SEDIMENT IS OBSERVED IN THESE AREAS, THE CONTRACTOR SHALL RELOCATE OR INSTALL ADDITIONAL FILTREXX FILTER SOXX IN LOCATIONS THAT CAN BE STAKED. THIS WORK IS INCLUDED IN THE PROJECT SCOPE.
- 11. SILT FENCE OR STAKED HAYBALES MAY BE USED IN LIEU OF FILTREXX FILTER SOXX.

10/14/2020

DATE

12. AN ALTERNATE COMPOST SOCK OR STRAW WATTLE PRODUCT MAY BE USED IN LIEU OF FILTREXX FILTER SOXX UPON APPROVAL OF THE ENGINEER.

IN AREAS W/ LESS THAN 12% SLOPE. TO CONSTITUTE AN ORIGINAL PLAN 10 FT. MIN. FROM FOUNDATIONS. 15 FT. MIN. FROM ONSITE WASTEWATER TREATMENT SYSTEMS. 25 FT. MIN. FROM PRIVATE DRINKING WATER. SEE TABLE 1 OF THE RI STORMWATER MANAGEMENT GUIDANCE FOR INDIVIDUAL SINGLE-FAMILY RESIDENTIAL LOT DEVELOPMENT FOR ADDITIONAL SETBACKS. SHOULD BE CONSTRUCTED ALONG THE DOWNHILL SIDE OF THE RAIN GARDEN, PERPENDICULAR TO THE SLOPE OF THE LAWN. SELECT NATIVE PLANTS FOR RAIN GARDEN USING THE COASTAL PLANT GUIDE (www.uri.edu/cels/ceoc/coastalPlants/CoastalPlantGuide.htm) OR APPENDIX B OF THE RI STORMWATER DESIGN & INSTALLATION STANDARDS MANUAL. ROOF LEADER PIPE SLOPE CRUSHED STONE ENTRANCE OR SWALE SLOPE TO PREVENT CHANNELING TO RAIN GARDEN BMP = 2.0 % MIN.**DEPRESSION** PONDING AREA (1200 SQ. FT. MIN.) **DEPRESSION** SHOULD BE LEVEL SOILS WITHIN THE RAIN GARDEN AREA ARE NOT TO BE COMPACTED. IF SOILS DO BECOME COMPACTED, IT IS TO BE TILLED AND AMENDED TO MAINTAIN PROPER 2-3 INCH LAYER OF NON-DYED AGED DRAINAGE. 2-4 INCHES AMENDED SOIL LAYER. SHREDDED HARDWOOD MULCH. AMENDED SOIL LAYER SHOULD BE A 50/50 MIXTURE OF THE EXCAVATED NATIVE SOIL &

RAIN GARDEN 1 DETAIL

MATURE ORGANIC COMPOST.

<u>NOTES</u>

- 1. RAIN GARDENS SHALL BE INSPECTED FOLLOWING AT LEAST THE FIRST TWO PRECIPITATION EVENTS OF AT LEAST 1.0 INCH TO ENSURE THAT THE SYSTEM IS FUNCTIONING PROPERLY. THEREAFTER, THE RAIN GARDEN SHALL BE MONITORED AND MAINTAINED TO ASSURE PROPER FUNCTIONING, PLANT GROWTH AND SURVIVAL. PLANTS SHALL BE REPLACED ON AN AS-NEEDED BASIS DURING GROWING SEASON.
- 2. SILTS/SEDIMENT SHALL BE REMOVED FROM THE RAIN GARDEN WHEN ACCUMULATION EXCEEDS ONE INCH, OR WHEN WATER PONDS ON THE SURFACE OF THE RAIN GARDEN FOR MORE THAN 48 HOURS. THE TOP FEW INCHES OF MATERIAL SHALL BE REMOVED AND SHALL BE REPLACED WITH FRESH SOIL MIXTURE & MULCH.
- 3. PRUNING OR REPLACEMENT OF WOODY VEGETATION SHALL OCCUR WHEN DEAD OR DYING VEGETATION IS OBSERVED.
- 4. SOIL EROSION GULLIES SHALL BE REPAIRED AS THEY OCCUR.
- 5. FERTILIZER OR PESTICIDES SHALL NOT BE APPLIED TO PLANTS WITHIN RAIN GARDENS.
- 6. PERENNIAL PLANTS AND GROUND COVER SHALL BE REPLACED AS NECESSARY TO MAINTAIN AN ADEQUATE VEGETATED GROUND COVER, ANNUAL PLANTS MAY ALSO BE USED TO MAINTAIN GROUND COVER.

COPYRIGHT

1. WHARF ROAD

2. GLENCO ROAD

3. FLORA STREET



RIGL 34-13-1

ABUTTING STREET INDEX

THESE DRAWINGS ARE THE PROPERTY OF THE ENGINEER/SURVEYOR AND HAVE BEEN PREPARED FOR THE OWNER, FOR THIS PROJECT AT THIS SITE AND ARE NOT TO BE USED FOR ANY OTHER PURPOSE, LOCATION OR OWNER WITHOUT WRITTEN CONSENT OF THIS OWNER OR ONE OF IT'S DIRECTORS'

WARWICK, RHODE ISLAND SHM GREENWICH BAY, LLC 6033 2023 Site rev2 14785 PRESTON ROAD, SUITE 975 3 of <u>5</u> SHTS DALLAS, TEXAS 75254

MINOR PLAN REVISIONS AS REQUESTED BY CLIENT

DETAIL PLAN 1 GREENWICH BAY MARINA EAST YARD PLAT

GLENCO ROAD, FLORA STREET & WHARF ROAD

ADDED ZONING INFORMATION & UPDATED EX. POOL AREA

REVISED PROPOSED WORKSHOP LOCATION ON SITE PLAN

46 Sutton Avenue East Providence, RI Phone: (401) - 438 - 5775 Fax: (401) - 438 - 5773

BJT


RSL

CHECKED BY


AS NOTEL

BJT/MS RSL/LRS


C-2



** SIGNATURES MUST BE IN BLUE INK TO CONSTITUTE AN ORIGINAL PLAN



FILTREXX® FILTER SOXX™ SECTION




FILTREXX® FILTER SOXX™ SECTION


NOTES:

- 1. FILTREXX FILTER SOXX MAY BE USED IN LIEU OF SILT FENCE.
- 2. CONTRACTOR IS RESPONSIBLE TO BECOME FAMILIAR WITH THE FILTREXX PRODUCTS AND COORDINATE INSTALLATION SCHEDULES AND METHODS WITH ENGINEER PRIOR TO PLACEMENT.
- 3. ALL MATERIAL SHALL MEET FILTREXX SPECIFICATIONS.
- 4. COMPOST MATERIAL TO BE DISPERSED ON SITE AS DETERMINED BY ENGINEER.

FILTREXX® FILTER SOXX™ DETAIL



ROOF LEADER DETAIL



CONSTRUCTION ENTRANCE DETAIL
(N.T.S.)

RIGL 34-13-1 ABUTTING STREET INDEX

1. WHARF ROAD
2. GLENCO ROAD
3. FLORA STREET

COPYRIGHT

WATERMAN ENGINEERING CO.
CIVIL ENGINEERS & SURVEYORS
46 SUTTON AVENUE
EAST PROVIDENCE, RI 02914-2096

THESE DRAWINGS ARE THE PROPERTY OF THE ENGINEER/SURVEYOR AND HAVE BEEN PREPARED FOR THE OWNER, FOR THIS PROJECT AT THIS SITE AND ARE NOT TO BE USED FOR ANY OTHER PURPOSE, LOCATION OR OWNER WITHOUT WRITTEN CONSENT OF THIS OWNER OR ONE OF IT'S DIRECTORS'





46 Sutton Avenue East Providence, RI Phone: (401) - 438 - 5775 Fax: (401) - 438 - 5773 www.watermanengineering.net

